

5. *Departmental Tests.*—In addition to the general educational qualifications mentioned above, candidates for appointments may be required to pass such departmental tests as may be prescribed by Government from time to time.

6. As vacancies occur, the appointments will be made from the approved lists according to the relative order, mentioned therein, of the names of candidates.

7. The candidates must be prepared to take up service in any part of the Mysore State.

8. The appointed candidate will be started as a probationer in the unit of recruitment and will, on the cessation of the temporary or acting vacancy in which he is appointed, be, as far as possible, continued and provided in other vacancies of the same class till he is finally absorbed. He will ordinarily start only at the bottom of the service in the class to which he is appointed and will be on probation for a period of two years from the date on which he joins duty. He will also be liable for transfer to any part of the State.

9. Intending candidates should submit their applications, in duplicate, in the prescribed form together with copies of testimonials, etc., so as to reach the undersigned on or before the 31st July 1936. Candidates in service should submit their applications through their official superiors. Those applying for more than one kind of appointments should submit separate applications in respect of each.

10. No notice will be taken of applications that are received after the due date or are not submitted in the prescribed form or do not furnish all the particulars required in the various columns of the form. Applications for services other than those referred to in para 1 above will not be considered.

By Order,
J. B. MALLARADHYA,
Secretary,
Central Recruitment Board.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 21st July 1936.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 12 Noon on 4th August 1936, for constructing the First Floor over the Central Block of the Law Court Buildings at Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of Rupee one for each form should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing the First Floor over the Central Block of the Law Court Buildings at Mysore." The name of the tenderer should also be superscribed on the sealed Cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 in words (one thousand rupees only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 4th August 1936 at 3 P.M. The final acceptance of the tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the Agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings, may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures. Tenderers offering a percentage reduction on the estimate amount will be rejected.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the Contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney, authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate and are liable to alterations, omissions, deductions, or additions, at the discretion of the Assistant Engineer, or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

16. The work should be completed and handed over to the Public Works Department within two months from the date from which the work is ordered to be commenced, failing which the Assistant Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will be recovered from the Contractor's outstandings for the period exceeding by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipts originally granted, along with an application, to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages, for delays caused by Officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The Contract should not be sub-let.

21. All materials, tools and plant and machinery, old doors, windows, etc., that will be supplied by the Assistant Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderers will pay the hire, etc., on Machinery and tools and plant at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores. The dates considered being, the dates of acknowledgments of the vouchers in each transaction.

22. The Contractors should arrange for the payment of Royalty and Tolls.

Note (A).—The Contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labours required in setting out the works.
- (2) Provide all necessary scaffolding, centering labour and appliance for hoisting.
- (3) Provide mortar mill and shed to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry tile pieces to steps, sieves, parabs, or measures shoring and other requisite protection during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
- (9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
- (10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note (B).—It is the business of the Contractor to make his own arrangements for the quarries and supplies of materials.

23. The rates for wood work for all works quoted, should be based on the rates of the departmental supply as noted below. Only Mysore Teak selected from the Mysore Depots must be used. Prevailing Government rates at Mysore Forest Depot for—

		Rs.	a.	p.	
(1) Selected 1st class logs	..	2	8	0	per c.ft.
(2) Cut scantling of sizes	..	3	4	0	„ for sizes 3"×4".
(2) (a) Do	..	3	12	0	„ for sizes 3"×5" to 4"×7".
(3) Planks 1" to 1½" of required sizes	..	4	8	0	„

24. If it is considered desirable, the work will be distributed to more than one contractor for the speedy completion of the work.

Abstract estimate for constructing First Floor over the Central Block of Law Courts at Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
GROUND FLOOR.			Ra. a. p.		
<i>Extending verandah in the rear.</i>					
1	Earthwork excavating foundation and filling in basement	C.yds.	..	26	
2	Chunam concrete with broken 1: 2: 4 granite jelly (size 1" to 1½")	C.ft.	..	174	
3	Burnt brick in chunam mortar 1: 2	"	..	1,607	
4	Arch work with burnt brick in chunam mortar 1: 2 semi-circular three rings of 4½" thick with cementing, etc.	"	..	118	
5	Chunam plastering	Sqr.	..	25·60	
6	White and colour washing	"	..	25·60	
7	Providing rolled steel girders tested including fixing in cement concrete and hoisting with a coat of anti-corrosive painting, etc., complete	Cwt.	..	139	
8	Burnt stone slabs 6" thick dressed and fixed	S.ft.	..	115	
9	Cement concrete in place of 1: 2: 4 wall plate	Sqr.	..	4·26	
10	(a) Reinforced brick in cement concrete terrace 1: 2: 4 with ½" reinforcement 6" from centre to centre and negative bending reinforcement with 2" long and 1" cross joints filled with cement concrete slab 2" thick and ¾" thick, cement plastered flooring including tile colouring and cutting tiles and ceiling, plastering, etc., complete as per specification	"	..	31·80	
	(b) Do do with ¾" reinforcement	"	..	..	
	(c) Reinforced cement concrete (with other details noted above 10 (a) Reinforcement as per design to be approved during execution.	"	..	..	
11	Reinforced joist and brick nogged terrace with 4" koppi in quick lime and two courses of flat tiles top and bottom plastering, etc., complete.	"	..	4·20	
12	Cornice 12" thick as per existing design	R.ft.	..	116	
13	Balestrated parapet as per existing design	"	..	58	
14	Constructing teakwood geometrical staircase with hand and top railing at wall, etc., complete	Each step	..	50	

N.B.—All protection works to be done by contractors themselves, at their own cost, during execution of work.

No.	Items of work	Unit	Rate	Quantity	Cost
FIRST FLOOR.			Rs. a. p.		
1	Dismantling masonry and carting debris	C.ft.	..	848	
2	Removing sloping terrace roof and refixing the wooden panel work over First Floor	Sqr.	..	46·48	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
3	Burnt brick in mortar 1 : 2	C.ft.	..	10,461	
4	Do semicircular arch work with 3 rings of 4½" including cementing, etc. ..	"	..	1,198	
5	Roofing with reinforced joists and brick nogged terrace with 4" koppi in quick lime and two courses of flat tiles, top and bottom plastering etc., complete	..	..	43.90	
6	Do with pukka terrace as per existing design including masonry ridging etc., complete	Sqr.	..	42.70	
	(b) Do flat terrace	"	..	3.78	
7	(a) Removing and fixing doors	No.	..	22	
	(b) Closing gaps with burnt brick in mud including chunam plastering on both sides ..	C.ft.	..	1,025	
	(c) Do with brick in chunam	"	..	1,025	
8	Providing teakwood windows with glazed shutters 1½" thick and ⅝" thick glasses with iron fixtures, etc., without iron bars	S.ft.	..	330	
9	Do semicircular Fan lights with (¾" dia.) iron bars, glazed shutters, etc., complete	"	..	78	
10	Cement concrete 1 : 2 : 4 in place of wall plate ..	Sqr.	..	4.74	
11	Chunam plastering 1 : 2	..	..	241.00	
12	White and colour washing 2 coats	"	..	241.00	
13	Painting two coats with Delux Burnswick with green and varnishing inside (Tint to be approved during execution)	"	..	31.00	
14	(a) Cornice (Dental) ornamental as per existing design	R.ft.	..	112	
	(b) Do ordinary 12" thick as per existing design	"	..	553	
15	Constructing parapet (9"×3') with brick in chunam and baluster pannels as per existing design	"	..	465	
16	Ornamental works as per existing design ..	Item	..	1	

S. RAMASWAMY,
Assistant Engineer.